

DC FAST CHARGER • 80 KW DUAL CCS2

Galaxy V Series 80kW

Ultra Slim DC Charging Station with dual CCS2 connectors, and 2.3kW domestic socket.



2× CCS2 DC (200–1000 VDC, up to 200A) + 1× Type E 2.3 kW AC • Spring Cable Management (5m)

80 kW Dual CCS2 + 2.3 kW AC

Space-efficient ultra-slim footprint • $\geq 97\%$ peak efficiency @ full load

15.6" Touch Display & 270° Halo

270° RGB halo top lighting, RFID wave charging LED & 4× LED buttons

Tailored Payment & RFID

Dynamic QR code, The Charge Grid App, RFID & contactless payment

OCPP 1.6J / 2.0.1 & ISO 15118

Dual 4G LTE, Ethernet 10/100 Mbps, Modbus TCP & RESTful API

• The Charge Grid • DC High-Speed Charging Infrastructure

CE • Eichrecht • IP55 / IK10 • ISO 15118

Galaxy V Series 80kW

DC FAST CHARGER • 80 KW DUAL CCS2

Space-Efficient installation

Tailored payment

Hybrid charging

24/7 smart remote mgmt.

GENERAL INFO

Input Rating	400VAC±10%, 50/60Hz, L1+L2+L3+N+PE
Power Factor	≥0.99 @ full load
Efficiency	≥97% @ full load (peak)
Grid Type	TN-S, TN-C, TN-C-S, TT
Output Interface	2× CCS2, 1× Type E socket (optional)
Output Power	CCS2: Up to 80kW, Type E: 2.3kW
Output Voltage	CCS2: 200-1000VDC, AC: 230/400VAC ±10%
DC Output Current	Up to 200A

USER INTERFACE

Display	15.6 inch
Support Language	EN/DE/FR/ES/IT/NL/PT (others on request)
HMI	270° RGB halo top lighting, RFID wave charging LED, 4× illuminated LED buttons
User Authentication	RFID badges (up to 500 local badges), dynamic QR code, The Charge Grid App, contactless payment (optional)
RFID Reader	ISO/IEC 14443 A/B, ISO/IEC 18092, IEC/ISO 15693

COMMUNICATION

Network Interface	Dual 4G LTE, Ethernet 10/100 Mbps
Protocol (EVSE & Backend)	OCPP 1.6J, OCPP 2.0.1/2.1 ready
Protocol (EVSE & EV)	DIN70121, ISO 15118-2/-20
Commissioning	WebConfig via LAN/WLAN
EMS Integration	Modbus TCP, RESTful API

ENVIRONMENTAL

Operating Temperature	-30°C to +50°C (derating may apply)
Storage Temperature	-40°C to +70°C
Humidity	5% to 95% (non-condensing)
Altitude	≤2000m above sea level

MECHANICAL

IP Rating	IP55
IK Rating	IK10 (front housing), IK08 (tamper-resistant glass), IK07 (payment terminal)
Cooling	Forced-air cooling
Charging Cable Length	5m total cable length, 4.2m effective reach
Cable Management System	Spring
Installation	Ground-mounted

CERTIFICATION

Standards & compliance	IEC 61851-1, IEC 61851-21-2, IEC 61851-23, LVD 2014/35/EU, RED 2014/53/EU, EN 18031
Certification	CE, Eichrecht (optional)